

Dawkins Road: Bridge over Litzenburg Drain

(DES# 0500069)

Project Description

This is a bridge replacement project. The new bridge will be designed to accommodate vehicles with a larger turning path than the existing layout allows. This will require a wider bridge because the State Line Road intersection is located ten feet to the east of the bridge. The bridge and roadway width will taper down from the intersection to match the width of the existing pavement to the west. The new bridge roadway width will vary from 36' to 39'. New guardrails will be installed at the ends of the bridge. A new culvert pipe and field entrance will be constructed on the southwest side of the bridge.

The construction phase of this project is scheduled for 2011. The funding for this project is provided through the Group IV-Bridge program.

The following is the cost breakdown for the Dawkins Road project.

| Project Phase | Estimated Cost | Fiscal Year | Federal Share | State Share | Local Share |
|---------------|----------------|-------------|---------------|-------------|-------------|
| CN | 474,000 | 2011 | 379,200 | 0 | 94,800 |

The local agency responsible for this project is the Allen County Highway Department. You may contact the Engineering Department at 449-7369, if you have any questions or comments.

